


# Good Neighbor Authority Sale Area Map

## Wisconsin Department of Natural Resources

Moose Links Sale  
 Great Divide Ranger District  
 T41N R4W Sections 5, 6, 7 and 8  
 Tract 8003-1-21




This map is not a survey of the actual boundary of any property this map depicts.

### Legend

- Proposed Road
- Stand Line
- CNNF\_Roads
- Orange Line
- Natural Line
- Red Line
- Shelterwood
- Northern Hardwood Thinning
- Aspen Coppice
- Seasonally Restricted Area
- Roads

- Aspen Coppice (299 acres): Cut all trees greater than 2" except for orange marked trees, white pine, red pine, red oak, hemlock, northern white cedar, yellow birch and tamarack.
- Northern Hardwood Thinning (37 acres): Cut all trees marked with blue paint. Cut all trees >1 inch within purple marked gaps.
- Shelterwood (6 acres): Cut all trees containing one or more pulpsticks except for orange marked trees and pine.



Sale Prepared by:  
 Kyle Cummings  
 Sawyer County Forester



# Good Neighbor Authority Timber Sale

Moose Links Sale

Great Divide Ranger District

Chequamegon-Nicolet National Forest

**Tract #.** 8003-01-21

**Location:**

Town	Range	Section	Description
41N	4W	5	SW1/4, SWSE
41N	4W	6	E1/2NW, SW1/4 S1/2NE, SE1/4
41N	4W	7	N1/2NW, N1/2NE
41N	4W	8	N1/2NW

**Sale Area:** 342 Acres

SPECIES	VOLUME
Aspen	5,350 CDS
Mxd Hdwd	2,415 CDS
Balsam Fir	340 CDS
W. Spruce	220 CDS
Basswood	25 CDS
Mxd Hdwd	43 MBF
Basswood	6 MBF
Sugar Maple	11 MBF

- Aspen 4500 lbs. per cord or 2.25 tons per cord.
- Mixed hardwood 4740lbs. per cord or 2.37 tons per cord.
- Basswood 3850 lbs. per cord or 1.925 tons per cord.
- White spruce 4000 lbs. per cord or 2.00 tons per cord.
- Balsam fir 4250 lbs. per cord or 2.125 tons per cord.

**Minimum Bid Value: \$108,979.50**

- Mixed hardwood pulpwood is: 42% Red Maple, 39% White Birch, 17% Sugar Maple, 1% White Ash and 1% Black Ash.
- Mixed hardwood logs are: 21% Red Maple, 69% White Birch and 10% Black Ash.

**Harvest Requirements:**

**C. 67 S. 6, 9, 12, 16, 20, 21, 26, 29, 72 (Aspen Coppice-299 Acres):** Cut all trees greater than 2" except for orange marked trees, white pine, red pine, red oak, hemlock, northern white cedar, yellow birch and tamarack.

**C. 67 S. 7 (Birch Shelterwood-6 Acres):** Cut all trees containing one or more pulpsticks except for orange marked trees and pine.

**C. 67 S. 17, 21 (Northern Hardwood Thinning-37 Acres):** Cut all trees marked with blue paint. Cut all trees >1 inch within purple marked gaps.

**Additional Requirements:**

- **This Contract Period is 3 years. Contract End Date is January 1, 2025.**
- **Seasonally Restricted Area: No harvest or road usage within this area from April 1-October 1. Compartment 67 Stand 6 and 9 are restricted to winter only, for all other stands harvesting operations may occur during dry or frozen conditions.**

- Provide for an average of one ruffed grouse drumming log for every 10 acres of aspen clearcut. The log should be 10 inches or more in diameter and at least 12 feet long
- All slash must be kept clear of travel ways at all times, removed from the area 10 feet from road edges and along private lands, kept out of wetlands and riparian areas, and lopped/scattered within 2 feet of ground.
- Sale bounded by orange paint, red paint, FR 173 and natural boundaries. See sale maps for specifics.
- Do not harvest trees or operate equipment across Orange line.
- Sale will be billed using mill ticket system.
- No bid bond required, a performance bond of 15% of the total sale bid value will be required.
- Reserve all snags that do not pose a safety risk.
- Equipment must be clean of dirt and debris before entering sale area.
- Forest plan requires that all native surfaced approaches to paved or graveled roads have 100' of gravel put down when used during non-frozen conditions.
- Safety signs are required on public trails and roads entering active harvest areas.
- All landings and skid trails will be blocked to vehicular access and possibly re-seeded at the conclusion of use if needed.
- Temporary Roads shall have the road base constructed to a width of 12 feet or narrower, and with vegetative clearing of trees and brush not to exceed a width of 25 feet. Exceptions to the 12 foot maximum width of the road base may be granted by the sale administrator. Exceptions would typically be granted for sections of temporary roads where tight turns, curves, and terrain create a need so that trucks and equipment can be operated safely. All existing berms must be replaced upon completion of the sale.
- **The forest plan indicated Road ID, FR160A, FR160B, FR160C, W230250, W230251, W230252 must be decommissioned following sale.**
- All road maintenance and rehabilitation post-harvest is the purchaser's responsibility. A sample contract including road maintenance specifications can be obtained by request.
- All Temporary Roads and other Roads noted in the contract for use in Sale will be decommissioned when sale is completed.
- Road maintenance and restrictions details are listed in the timber sale contract. Please contact a forester listed on the sale map for more information.
- The harvesting of any portion of a tree that lies outside the physical ownership of the Forest Service will not be allowed. Trees lying across the property line must be bucked at the ownership line and all portions of the tree that reside on the private side of the line must be left in place. Conversely, the remaining portion of the tree that lies within the physical ownership of the Forest Service may be harvested and utilized.