

Tract 12-21 (Rumble Strip Sale)

Parts of: NW, W1/2 NE, SW Sec. 3; N1/2 NW Sec. 10, T 39N-R3W, Sawyer County.

95 Acres

<u>Species</u>	<u>Estimated Volume</u>	
¹ Mixed Pulp	900 tons	
Aspen	2500 tons	Minimum Acceptable
² Balsam Fir	875 tons	<u>Bid for Entire Sale</u>
		\$31,512.50

¹Mixed pulp includes 44% hard maple, 42% red maple, 4% ash, 6% yellow/white birch, 2% basswood, and 2% ironwood and elm combined.

²Balsam Fir includes 91% balsam fir, 8% spruce, and 1% tamarack.

Other species not mentioned will be charged at the mixed pulp price.

The performance bond will be 15% of the total sale value. Contract ending date will be June 30, 2024.

SPECIAL SALE CONDITIONS:

Equipment use will be restricted to very dry or frozen ground conditions due to wet soil conditions. Some areas will require frozen conditions due to access.

No harvesting in the selection area during the months of April, May, and June due to bark being easily damaged these times.

No decking or skidding on the Tuscobia trail. All wood harvested along the Tuscobia trail shall be decked behind the 50-foot buffer on existing back-ins. There is a 50-foot "no-cut" buffer along the trail that has been lined out with yellow paint.

Hauling on the Tuscobia trail shall only be conducted Monday through Friday. **No hauling on the weekends.**

Proposed roads/skid trails are indicated on map and shall be used to access the harvest areas. Modifications may be made with approval of forester. Other new construction must be approved by forester.

The trail entrances off Cty. Rd. EE will most likely need pit run material if used during non-frozen conditions. The state will provide the pit run material, but it will be the responsibility of the contractor for loading/hauling/leveling any pit run needed for these entrance roads.

No access from Hwy. 70 due to steep bank.

Debris berms are required at locations designated on map.

All slash located within 100 feet of Cty. Rd. EE, Hwy. 70 and the Tuscobia trail shall be lopped and scattered to within two feet of the ground. No slash will be left in ditch line of Cty. Rd. EE or within 50' of either side of the Tuscobia trail.

No slash or logging debris will be left across the blue line.

3" of packed snow will be maintained on the Tuscobia trail, weather permitting. **The trail will be kept free of debris.**

The contractor is responsible for repairing any damage done to the gate.

There are small areas within the coppice area (indicated on the map) that have wind damage. These areas are included within the sale. Utilize merchantable trees from the wind damaged areas. Wind damage is defined as uprooted or trees with 50% or more crown damage.

All additional restrictions listed in prospectus and standard contract apply unless specified.