

Tract 9-24 (Ferns Forever) – Flambeau River State Forest
Parts of: S1/2 NW, SW Sec. 21, T39N-R3W, Town of Draper, Sawyer County

93 Acres

<u>Species</u>	<u>Estimated Volume</u>	
¹ Mixed Pulp	3750 tons	Minimum Acceptable
Basswood	230 tons	<u>Bid for Entire Sale</u>
Aspen	180 tons	\$ 51,306.00
Balsam Fir	280 tons	
Hard Maple	140 MBF	
Ash	19 MBF	
Basswood	33 MBF	
² Mixed Saw	3 MBF	

Utilization specifications for cordwood will be 1 stick (100 inches) to a 6-inch top diameter.

¹Mixed pulp includes 89% hard maple, 7% ash, 3% white birch, and 1% red maple.

²Mixed saw is primarily red maple.

Other species not mentioned will be charged at the mixed pulp/saw price.

The performance bond will be 15% of the total sale value. Contract ending date will be **June 30, 2027**.

SPECIAL SALE CONDITIONS:

Equipment use will be allowed during very dry or frozen ground conditions.

Harvesting shall occur between July 1st – March 31st in selection area and overstory removal area due to softness of bark.

Use of a continuous rotating saw head will not be allowed on sale due to density and distribution of regeneration.

If decking on state forest road, all slash and ends will be removed from the roads and ditches concurrently with each truckload.

Existing woods trails will be used. New road construction will be limited to the proposed road location layout on prospectus map. Modifications may be made with approval of forester.

A stream crossing permit is needed to access the sale. The permit has been obtained by the Flambeau River State Forest. The design will be a temporary bridge, clear spanning the stream where no material will be placed below the OHWM (Ordinary High Water Mark). If the logger cannot span the stream with standard timber mats, 24–30-foot tree poles will be needed. Timber mats would then be placed on these poles. All conditions of the stream crossing permit will be followed by the contractor.

To make areas of sale operable during dry conditions, existing trails and proposed woods trails will most likely need pit run material. The state will provide the pit run material, but it will be the responsibility of the contractor for loading/hauling/leveling any pit run needed for these existing roads and proposed road. All BMPs for water quality shall be followed.

Payne Farm Road may be used for multiple timber sales. It is the responsibility of the contractors to determine logistics for hauling and road maintenance/repairs.

All additional restrictions listed in prospectus and standard contract apply unless specified.

Contact Heidi Brunkow with questions and the combination to the gate lock at 715-332-5271 ext. 106 or heidi.brunkow@wisconsin.gov. **Please do not go around gates.**