


**WISCONSIN
DEPARTMENT OF NATURAL RESOURCES
TIMBER SALE
TRACT 12-20 ROCK PILE FARM
T43N R5E SECTIONS 6 & 7
HARVEST ACRES - 77**



Legend

- Gates
- Section Corner
- Survey Marker
- Keg/Swamp/Wet Seep
- Blue Line
- Red Line
- Woods Roads
- Highways and Town Roads
- Rivers and Streams
- Grassy Opening
- Lakes

All stands are within Mgmt. Area 1:
Winegar Moraines -
Forest Production



Harvest Area (77 Acres): Cut all merchantable aspen, maple, ash, ironwood and balsam fir. Cut only the spruce marked with orange paint on the NORTH side of Bruette Road. Cut all spruce SOUTH of Bruette Road unless marked with green paint.

Note: Do not cut any white birch or any trees marked with green paint.



Scale: 4" = 1 Mile
1:15,840



Map produced by
Todd Anderson &
Paul Schultz, 8/21

This map is not a survey
of the actual boundary of
any property this map depicts.

NH-ALSF TRACT NO. 12-20
Rock Pile Farm

Vilas County

Township 43 North, Range 5 East

Section 6 – SESW, NESE, SWSE and SESE

Section 7 – NENE, NWNE and NENW

The cutting area is approximately 77 acres.

The contract period is 3 years.

All trees that will yield one or more 100-inch sticks to the minimum top diameter chosen by the bidder will be cut and utilized.

Whole tree harvest is allowed on this timber sale.

ESTIMATED VOLUME (TONS)
MINIMUM TOP DIAMETER

<u>SPECIES</u>	<u>4"</u>	<u>Whole Tree</u>
Balsam Fir ¹	670	890
Aspen	3750	5000
Mixed Hardwood ²	375	520

Total Minimum Bid Value \$ 24,066.00

The following is based upon volumes to a 4" top:

1\ Balsam Fir – Approximately 575 tons Balsam Fir and 95 tons White Spruce; included in this volume is approximately 11 MBF of
. White Spruce. Weighted average = 2.094 tons/cord.

2\ Mixed Hardwood – Approximately 284 tons Red Maple, 67 tons Sugar Maple, 15 tons Ironwood and 8 tons ash; included in this
. volume is approximately 4 MBF of Sugar Maple. Weighted average = 2.339 tons/cord.

Sale contains approximately 59 tons/acre or 27 cords/acre.

Special Conditions

1. Rutting will be monitored and if soil disturbances become excessive (based on established thresholds defined in the contract), harvesting operations may be suspended until the affected areas are repaired properly. Harvesting may not resume until field conditions improve sufficiently to avoid rutting.
2. All landings and any new roads must be approved prior to sale start up. All roads must be cleared of debris and leveled upon sale completion.
3. Slash within 50 feet of the Town Road must be lopped and scattered within 2 feet of the ground and pulled back at least 10 feet behind the tree line concurrently with cutting.
4. Do not operate machinery within 15 feet of any ephemeral pond or wetland and do not deposit any slash or tops in them.