

Tract 6-25 (LOP & Scatter) – Flambeau River State Forest

Parts of: E½SE, Section 10. W½SW, NESW, Section 11. NWNW, Section 14. E½NE, Section 15. T38N-R3W, Winter Township, Sawyer County.

117 acres

<u>Species</u>	<u>Estimated Volume</u>	
¹ Mixed Hardwood	2900 tons	
Aspen	1150 tons	
² Mixed Softwood	825 tons	Minimum Acceptable
³ Red Pine	180 tons	<u>Bid for Entire Sale</u>
Ash	39 MBF	\$39,640.00
⁴ Mixed Saw	27 MBF	

¹Mixed hardwood includes 36% ash, 30% red maple, 23% hard maple, 5% basswood, 3% white birch, 2% yellow birch, and 1% cherry, elm, and ironwood combined.

²Mixed softwood includes 62% tamarack, 36% spruce, and 2% balsam fir.

³Red pine includes 13 MBF sawtimber.

⁴Mixed saw includes 14 MBF red maple, 6 MBF basswood, 4 MBF hard maple, 3 MBF white and yellow birch combined.

Other species not mentioned will be charged at the mixed hardwood or saw price.

The performance bond will be 15% of the total sale value. **The contract end date is June 30, 2029**

SPECIAL SALE CONDITIONS:

This sale provides an opportunity to showcase sustainable forestry in a highly used area. Great care must be taken to avoid damage to signs, kiosks, trails, and other state forest property.

Portions of the hiking trail may be utilized as part of the timber sale. Care must be taken during operations to ensure safety of the trail users. Damage to the trail must be fixed immediately.

Seasonal and Equipment Conditions

No harvest operations are allowed on the entire sale from June 1st – August 16th. Additionally, the circled area of the map must be completed between Labor Day and Memorial Day weekend. Selection areas and thinnings must also occur outside of April and May due to bark being easily damaged during these times.

Equipment use will be restricted to very dry or frozen ground conditions due to wet soil conditions.

All pine cut or piled from March through August shall be removed within three weeks.

Roads/Access/Decking

No decking, forwarding, or skidding is allowed on Lake of the Pines Road or the State Forest Roads.

Access points on the east side of Lake of the Pines Road will be limited to the proposed back-in trails indicated on the map.

Contractor is required to place logging debris berms at designated locations on map.

For the hiking trail, all slash, ends, and debris must be removed from the trail concurrently with each truckload.

Proposed road construction is optional and is limited to proposed road layout shown on the map.

No slash or logging debris allowed on or within the ditch line of Lake of the Pines Road or hiking trail. All slash that is located within 100 feet of Lake of the Pines, Lake of the Pines Road, and the hiking trail shall be lopped and scattered to within two feet of the ground.

To make areas of sale operable during dry conditions, existing trails and new stub roads will most likely need pit run material. The state will provide the pit run material, but it will be the responsibility of the contractor for loading/hauling/leveling any pit run needed for decking on these existing roads and new stubs. Culvert placement was completed by the state.

All additional restrictions listed in prospectus and standard contract apply unless specified.

Contact Justin Cook with questions at 715-332-5271 Ext 109 or justin.cook@wisconsin.gov.